

# ROUND LAKE METRA COMMUTER LOT IMPROVEMENTS

## ADDENDUM NO. 1

MAY 6, 2016

1. **Schedule of Prices, Form BLR 12200a (page 5-2)** – Revised units for item numbers 32 and 34 from square yards to cubic yards to match schedule of quantities listed on cover sheet of plans.



**Illinois Department  
of Transportation**

**SCHEDULE OF PRICES**

County Lake  
 Local Public Agency Village of Round Lake  
 Section N/A  
 Route Metra Commuter Lot

**Schedule for Multiple Bids**

Combination Letter	Sections Included in Combinations	Total

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

**Bidder's Proposal for making Entire Improvements**

Item No.	Items	Unit	Quantity	Unit Price	Total
1	Barrier Curb Removal Complete	L.F.	210		
2	B-6.12 Curb & Gutter Removal Complete	L.F.	100		
3	B-6.24 Curb & Gutter Removal Complete	L.F.	25		
4	Barrier Curb	L.F.	220		
5	B-6.12 Curb & Gutter	L.F.	100		
6	B-6.24 Curb & Gutter	L.F.	37		
7	Saw-Cut for Existing Pavement Removal	L.F.	125		
8	Full Depth Asphalt Removal	SQ.YD.	5000		
9	Replace Adjusting Rings and Adjust Existing Storm Drainage Structure	EACH	1		
10	Install 5'x5' Concrete Collar Around Existing Storm Drainage Structure	EACH	3		
11	6' Concrete Walk w/ Integral Curb (Accessible Route Reconstruction)	SQ.YD.	3		
12	Detectable Warning Removal & Replacement	EACH	1		
13	Detectable Warnings	EACH	1		
14	Grading of Existing Aggregate Base Course Complete	SQ.YD.	5000		
15	1 1/2" HMA Surface Course	SQ.YD.	5000		
16	2 1/4" HMA Binder Course	SQ.YD.	5000		
17	7" HMA Binder Course (IDOT Pavement)	SQ.YD.	160		
18	4" CA-6 Crushed Stone (IDOT Pavement)	SQ.YD.	160		
19	Thermoplastic Pavement Striping (4" Solid White)	L.F.	2600		

**RETURN WITH BID**

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
20	Thermoplastic Pavement Markings (24" Stop Bar, White)	EACH	2		
21	Thermoplastic Pavement Markings (Cross-walk, White)	L.S.	1		
22	Thermoplastic Pavement Markings (Accessible Parking Stalls Complete, Yellow)	EACH	10		
23	Pavement Markings (16" Tall Parking Stall Numbering, Yellow)	EACH	96		
24	3" HMA Surface Course (At Bike Racks)	SQ.YD.	23		
25	Concrete Walk (At Proposed Bike Racks)	SQ.YD.	26		
26	Signage Complete	EACH	3		
27	Signage (Accessible Parking Stalls Complete)	EACH	10		
28	Bike Racks Complete	EACH	4		
29	Swale Grading	SQ.YD.	50		
30	Restoration and Seeding	SQ.YD.	250		
31	Traffic Control & Protection	L.S.	1		
32	Removal and Disposal of Unsuitable Materials	C.Y.	250		
33	Geotextile Fabric	SQ.YD.	250		
34	Aggregate Subgrade Improvement	C.Y.	250		
35	IDOT Bond (\$30,000)	L.S.	1		
36	Metra Right of Entry Agreement Fee	L.S.	1		
37	Metra Railroad Protective Liability Insurance	L.S.	1		
38	Metra Flagger	DAYS	15		